

## Asphalt Company – Steam Piping

**Client Name and Location:** Withheld – Southern California, USA

**Date of Application:** June 2014

**Mascoat Representative:** Travis Creech

**Applicator:** Internal Paint Crew

**Coating Used:** Mascoat Industrial-DTI

**Primers:** Existing coating system, which was cleaned with acetone before application of the insulating coating.

**Application:** Steam Pipes

**Dimensions:** 3" pipe at various lengths

**Reason for Application:** Personnel Protection

**Mils Applied:** 120 mils (3.0 mm)

**Time to Complete:** 2 days

**Starting Surface Temperature:** 330°F (165.5°C)

**Post Surface Temperature:** Under 140°F (60°C), within PP5 (Personnel Protection for 5 Seconds) limits

**Quote from end user and/or applicator:** "These are small areas, but we have a ton of them around the plant that pose a hazard to workers. In a nasty environment like this, it is nice to have something we can put on and forget about."



**Prior to application**



**Post application**